



Oakwood University AI Studio & Engineering Lab

Turnkey proposal & execute-ready estimate for a 10-seat AI production studio, a hands-on engineering/soldering makerspace, and the department-wide power, network, camera, and access-control infrastructure that protects the investment — orchestrated end-to-end by Island Development Crew.

Prepared: June 2026

Client: Dr. Shushannah Smith
Chair, Mathematics & Computer Science
Oakwood University · Cooper Complex Bldg B
Huntsville, AL · ssmith@oakwood.edu

Provider: Jonathan Isaac
Island Development Crew LLC
256-668-8248 · jon-isaac@islanddevcrew.com

What this is. A planning-grade, audit-aware General-Contractor proposal built from an on-site walkthrough (May 26, 2026), 16 verified site photographs, and current June-2026 vendor pricing with named Huntsville subcontractors. IDC orchestrates every trade under one accountable point of contact, one transparent fee, and one progress dashboard. *Figures are planning ranges; each line is re-quoted to a sealed vendor/sub bid before purchase.*

10-Seat AI Studio · Rm 409

Soldering/Math Lab · Rm 407

Engineering · Rm 305 + 310

UniFi + pfSense Network

UniFi Protect Cameras

Multi-Door Access

≥4 Bambu Lab Printers

2084 / Lennox Curriculum

RECOMMENDED EXECUTION — ALL-IN (IDC-ORCHESTRATED)

\$172,000

Range \$170,625 – \$198,498. Includes equipment, subbed facility work, GC coordination, contingency, and the 10% IDC orchestration fee. Title III grant-eligible portion ≈ \$93.5K; facility/capital portion ≈ \$60.1K.

Mobilization deposit initiates procurement & sub scheduling (see Payment Schedule, p.7).

Secure payment: [Island Dev Crew Stripe payment link](#)
(insert IDC Stripe link / Payment Link)

Signing: signature-ready PDF with direct blocks (p.7);
DocuSign / SignWell / Dropbox Sign accepted.

Department-Wide Vision (full robust build incl. dept cabling, dept cameras, Room-405 bathroom & raised floor) is presented on p.10 as the donor / naming-gift envelope at **\$245K–\$330K**.

The opportunity

Oakwood does not need another computer lab. It needs an **AI production studio** where Math & Computer Science students *ship* AI — apps, agents, fabricated hardware, and research artifacts — backed by reliable power, network, and security. As the only Seventh-day Adventist HBCU, Oakwood can also give students a credible **responsible-AI ethics** voice (curriculum, p.9).

Why IDC as GC

One orchestrator manages every vendor and Huntsville subcontractor (electrical, low-voltage, access, GC), holds a single **3–7% coordination markup** on subbed facility work and a transparent **10% orchestration fee**, and keeps faculty & administration informed through a live progress dashboard with weekly/monthly reports.

1 · Executive Summary & How to Read This

This package separates the project into the three quote families requested, because each draws on **different funding**. Selling all three as one grant line will be clawed back at audit.

Track	Scope	Planning range	Funding lane
Quote 1 — AI Studio + Engineering	Compute, Bambu fleet, soldering/CNC, AV + 3 boards, furniture, consumables, software	\$88.2K–\$98.8K	Mostly Title III grant-eligible
Quote 2 — Power / Electrical	Subpanel, dedicated circuits, raceway, raised floor, permits	\$54.4K–\$61.0K	Facility — NOT grant (capital / donor)
Quote 3 — Network + Cameras + Access	UniFi + pfSense, Protect cameras, 4-door Access; + structured cabling labor	Equip in Q1·Q3; cabling facility	Mixed (electronics grant / cabling facility)

2 · Two Tiers — Recommended vs. Vision

Recommended Execution — ~\$172,000 all-in Studio/lean compute, lab-focused facility scope (power + cabling to the labs + MDF; raised floor in the AI Studio only; <i>no</i> Room-405 bathroom). This is the number to commit to — it sits at the top of the \$150–175K band you targeted and is what the execute-ready invoice (p.7) bills. Sub-\$170K lever: a single-lab camera pilot or 2-door access pulls the point toward \$160–165K (your call).	Department-Wide Vision — \$245K–\$330K The full robust transformation: pooled compute (RTX PRO 6000), dept-wide cabling (80 drops + fiber), dept-wide cameras, full electrical, raised floor <i>plus</i> the Room-405 bathroom and dept room-mod, 5-door access. This is the donor / naming-gift envelope (p.10) — not an execution commitment today.
---	---

3 · The Funding Firewall (critical)

Title III covers **supplies** (<\$2,000/unit) and **equipment** (≥\$2,000/unit) tied to the academic mission, with an audit trail and a **June 30** spend pressure. It does **not** cover **facilities** — electrical service, structural cabling labor, raised floor, construction, HVAC, the bathroom. Quote 2 in full and the cabling-labor / door-install portions of Quote 3 must come from **capital, physical-plant, donor, or match funds**. (The grant-tag of each invoice line is shown on p.7.)

4 · Sequencing — two hard dependencies + 90-day plan

- **No compute energizes before Quote 2 circuits.** The RTX workstation (575–600W) and DGX nodes need the dedicated 20A/30A circuits first.
- **The studio is unusable before Quote 3 drops.** Room 409 currently has *one* data drop; the 10GbE backbone + new drops come before deployment.

Phase	Actions
Now → June 30 (grant window)	Lock education-priced POs for Quote 1 (quotes expire 14–30 days); commission the licensed-electrician load study; get the campus-IT vendor ruling (UniFi vs. Aruba/Cisco); confirm tax-exempt status + line-by-line grant eligibility.
30 days	Sealed sub bids (3 each: electrical, low-voltage, access, GC); permits; cabling + raised-floor design; finalize room dimensions & seat count.
90 days	Install power → cabling/network → compute → cameras/access → demo day . Display boards + dashboard go live; first cohort onboards.

5 · Existing-Conditions Assessment (Walkthrough, May 26 2026)

A true on-site assessment was performed with Dr. Smith. The conditions below — confirmed in the 16 verified photographs on p.4 — are what the three quotes resolve. Room → lab mapping:

Room	Becomes	Condition found (drives scope)
409	AI Studio (10–13 seats)	Dr. Smith's preferred room. One data drop ; breakers trip on space heaters; keep the dual smartboards (one Wacom) + 2 projectors; fire-egress concern.
407	Math & Soldering Lab	Convertible; empty built-in cabinetry stores the soldering bench; an "L-bend" fits a fume extractor; shared CS-circuitry + engineering.
305 + 310	Engineering Lab	305 = project room w/ benches, packing tables, a donated 3D printer. 310 downstairs = the "good room" with existing NVIDIA-GPU desktops to repurpose for AI hosting (saves the engineering budget).
MDF closet	Network core	"Frankenstein" — switch <i>and</i> fuse box in one closet (not to code); drops out ~monthly; breakers too old. The leverage point to fix infrastructure.
405	(Vision only)	Borrow space for a small unisex bathroom — <i>facility/donor scope, excluded from the recommended tier.</i>

Whole-complex conditions: no 90° angles (slanted walls/floors); 15 "Frankensteined" AC units; all windows need resealing; bare cinderblock, no insulation. These raise facility labor and are why the load study + sealed bids precede commitment.

In Dr. Smith's words

"I've only got the one data drop right there." — *(asked: in the entire room?)* — "Yes, that's it right there."

"These electrical units, they can't handle nothing... I got portable heaters... Boom." → "That means your breakers need to be updated."


"I know this is not to code. We're not supposed to have a closet next to the fuse box."

"The main objective: secure and always changing... nobody could copy it or retain that information." *(access control)*

"We want AI. We need power. Power is the number one thing you invest in."

6 · Photo Exhibit Addendum (verified on-site)

Each photograph was individually reviewed; captions describe what is actually in frame. Full-resolution files in /exhibits.



EX-01 · Rm 409: Teaching cart labeled "...MATH & COMP" fed by a **single surface-run outlet on bare cinderblock** — the core power/data need.



EX-03: Damaged low-voltage plate with **bare blue/yellow data wires hanging to the floor** — existing cabling is inadequate.



EX-09 · Rm 305: The department **already 3D-prints** (MakerBot-class) in a cluttered, unventilated corner — justifies the Bambu fleet + fume extraction.



EX-07: Reusable **blue engineering benches + pegboard**; this room already has a ceiling-cassette AC + projector. Trims furniture cost.




EX-05: Interactive panel on bare block with **exposed AV cabling**; a reusable blue cabinet at left.




EX-04: Dated 2-toggle ON/OFF control plate — the "confusing, unlabeled controls" finding.



EX-06: Fogged / seal-failed window — envelope & HVAC weakness; supports supplemental cooling for GPU heat.



EX-02: A single low duplex outlet serving a classroom zone — extension-cord dependence.




EX-12: Real Oakwood student research (prosthetic mitral valve; cancer-screening "DACs") — the program already produces serious work.



EX-08: Reusable steel storage cabinet — supports the "separate machines from supplies / lockable storage" plan.



EX-14: Classroom door + lockset — the multi-door access-control + labeling retrofit.



EX-13: HVAC diffuser on bare block — part of the 15-unit "Frankensteined" system.

Additional verified exhibits in /exhibits: EX-10 lecture seating to reconfigure · EX-11 building access corridor · EX-15 "Graduates" pride board · EX-16 lab counter with a single outlet. 27 of 71 photos were blocked from download; re-share to add more.

7 · Quote 1 — AI Studio + Engineering Lab (Title III grant-eligible)

AI Studio · Rm 409 10–13 high-memory seats so students run local models: 6× Framework Desktop 128GB (~\$2,851) + 4× Mac Studio M4 Max 64GB (~\$2,600) + 1× DGX Spark (\$4,699) + an RTX 5090 workstation + Jetson AGX Thor + Orin Nano kits + Synology NAS + rack UPS + an 85" demo wall . Keep the dual smartboards/2 projectors.	Math & Soldering · Rm 407 5–10× Hakko FX-888DX soldering stations + recirculating BOFA 3D PrintPRO -class fume/VOC extraction in the cabinetry/L-bend; bench instruments; an enclosed Carbide Nomad 3 CNC. Reuses the empty built-in cabinets.	Engineering · Rm 305 + 310 ≥4 Bambu Lab printers : H2D large-format + X1E enterprise + 3× P1S + AMS , enclosures, filament. Repurpose the existing NVIDIA-GPU desktops in 310 for AI hosting (10GbE NICs, RAM, IP-KVM) — engineering compute for near-zero new spend.
--	---	--

Division	Representative real SKUs (June 2026)	Planning range
AI Studio compute (lean)	Framework Desktop 128GB · Mac Studio M4 Max 64GB · DGX Spark · RTX 5090 WS · Jetson Thor/Orin · Synology DS1825+ · rack UPS	\$30,000–\$33,000
Engineering Bambu fleet + GPU repurposing	Bambu H2D AMS Combo ~\$2,199 · X1E ~\$2,649 · 3× P1S+AMS ~\$799 · BOFA PrintPRO 3 · Intel X550-T2 NICs · PiKVM V4	\$16,900–\$18,500
Soldering bench + CNC	5–10× Hakko FX-888DX (~\$135) · bench fume extraction · Carbide Nomad 3 ~\$2,800	\$8,000–\$9,000
AV: 3 hallway display boards + 85" studio demo wall	3× ~50" commercial displays + UniFi Connect signage/media players + mounts · 85" commercial demo wall ~\$4,600	\$8,250–\$9,120
Furniture (movable) · Consumables/safety · Software/warranty	Movable benches/chairs · filament/resin/PPE/flammables cabinet/ABC+Class-D extinguishers · licenses + extended warranty	\$9,800–\$11,900
Quote 1 grant-eligible subtotal (equipment + supplies)		\$88,242–\$98,820

Display / project boards (your spec): a board outside *each* of the three labs (409 / 407 / 305-310), auto-fed from in-room activity via UniFi Connect — "you see AI happening before you enter the room." **Per-semester access** + the **85" demo wall** make the studio look intentional and impressive. **Grant tag:** items ≥\$2,000/unit are EQUIPMENT; the many <\$2,000 items (Orin Nano, P1S, Hakko, cameras, NAS, UPS, switches) are SUPPLIES — confirm with the grants officer whether rack components aggregate to a capitalized system.

8 · Quote 2 — Power / Electrical (Facility · NOT grant · subbed + GC-managed)

Scope (lab-focused)	Planning range
100A lab subpanel · 14 dedicated 20A circuits · 2× 30A L5-30 UPS circuits · conduit/raceway on cinderblock · lab touch-ups · permits	\$34,000–\$37,000

Load calc (electrician verifies): ~7–9kW continuous / ~12kW peak (~60–75A @120V) → a dedicated 100A subpanel is the floor (NEC 125% continuous derating; resolve 120/240V vs 208V; size the CNC circuit for inrush). **Named Huntsville subs to bid:** Madison Electric, Pro Electric, Lee Company, Blake Brothers, Urban Electric.

9 · Quote 3 — Network + Wi-Fi + Cameras + Access (Mixed: electronics grant / cabling facility)

Division	Real SKUs (June 2026)	Range	Lane
UniFi core + pfSense	UniFi EnterpriseXG-24 (\$1,299) · 2× USW-Pro-Max-24-PoE (\$799) · UDM-Pro-Max (\$599) · Netgate 6100 MAX pfSense (\$999) · 42U rack	\$3,837–\$4,500	Grant (equip)
UniFi Protect cameras	UNVR-Pro (\$499) + 8TB surveillance HDDs · 10–12× G5/G6 Turret/Bullet (\$129–\$199) · AI Pro (\$499) for the print room	\$3,055–\$3,800	Grant (equip)
UniFi Access — 4 doors, rotating credentials	4–5× UA-Hub-Door (\$199) · G3 Reader Pro (\$379) at entry + G3 Readers (\$159) · fail-safe HES strikes/maglock + REX + DPS + install	\$8,400–\$9,000	Equip + install
Structured cabling — lab-focused (SUBBED)	Cat6A drops + patch panel + MDF rack rebuild (cabling labor = facility)	\$12,000–\$14,000	Facility

Per-semester rotating credentials are native to UniFi Access (PIN expiry windows, NFC card deactivation, mobile/Wallet revoke — create a "Fall-2026" group, set term dates, deactivate at end → every credential dies at once). **Everything in one pane** (UniFi OS) replaces the antiquated MDF. **Named Huntsville subs:** low-voltage — Travel Tech (256.970.4558), Interweave (256-837-2300), Heart Technologies (256-859-4000), State Systems; access — AAC Systems, Clear Link, LOCKTEC (256-881-9300), Tri-State Electrical.

ADA / egress & code: all locks specified **fail-safe** (release on power loss); maglocks tie to the fire panel with REX + marked push-to-exit; Huntsville AHJ sign-off required. A distinct low-voltage permit + fire/egress coordination is carried in Permits.

10 · Execute-Ready Invoice — Recommended Execution

Invoice basis: IDC (Jonathan Isaac) as General Contractor. Grant-eligible lines may be procured under Title III; facility lines are subbed and carry GC coordination. Re-quote each line to a sealed bid before purchase.

#	Line item	Amount (range)
I · Grant-Eligible Equipment & Supplies (Title III)		
1	AI Studio compute — studio/lean tier	\$30,000–\$33,000
2	Engineering Bambu fleet + GPU-PC repurposing	\$16,900–\$18,500
3	Soldering bench + CNC	\$8,000–\$9,000
4	Consumables / safety / storage	\$3,000–\$3,800
5	AV — 3 hallway display boards + 85" studio demo wall	\$8,250–\$9,120
6	UniFi network core + pfSense edge	\$3,837–\$4,500
7	UniFi Protect cameras — priority labs + key hallway	\$3,055–\$3,800
8	UniFi Access — 4 doors, per-semester rotating credentials	\$8,400–\$9,000
9	Furniture (movable lab/studio)	\$5,000–\$5,800
10	Software / licensing / extended warranty	\$1,800–\$2,300
Grant-eligible subtotal		\$88,242–\$98,820
II · Facility — Capital / Donor (NOT grant-eligible · SUBBED)		
11	Power / electrical — lab-focused (subpanel, circuits, raceway, permits)	\$34,000–\$37,000
12	Structured cabling — lab-focused (Cat6A drops, patch, MDF rebuild)	\$12,000–\$14,000
13	Raised access floor — AI Studio only (~300–400 sqft) + light room mod	\$8,000–\$10,000
14	Permits / insurance / freight	\$2,400–\$2,800
Facility subtotal		\$56,400–\$63,800
Direct cost (I + II)		\$144,642–\$162,620
III · GC Coordination, Contingency & IDC Fee		
15	GC coordination markup — 3–7% on the subbed facility base only	\$1,692–\$4,466
16	Contingency — 6–8% on (direct + markup); 2026 memory-price volatility	\$8,780–\$13,367
17	IDC Orchestration Fee — 10% of pre-fee subtotal	\$15,511–\$18,045
ALL-IN TOTAL · Recommended commitment \$172,000		\$170,625–\$198,498

Payment schedule (proposed)

- 25% mobilization — on signature; initiates procurement & sub scheduling.
- 50% progress — at equipment delivery + electrical/cabling rough-in.
- 25% completion — at commissioning, demo day, & closeout docs.

Pay deposit: IDC Stripe payment link (insert link)

Acceptance & signatures

Signature-ready; DocuSign / SignWell / Adobe / print-scan accepted.

Provider

Jonathan Isaac
Island Development Crew LLC
jon-isaac@islanddevcrew.com

Signature / Date

Client

Dr. Shushannah Smith
Oakwood University · Math & CS
ssmith@oakwood.edu

Signature / Date

11 · Curriculum Spine — 2084 / John Lennox (responsible-AI ethics for an Adventist HBCU)

Textbook: "2084 and the AI Revolution" (Updated & Expanded Ed., John C. Lennox, Zondervan Reflective 2024, ISBN 9780310166641, ~\$24–28) — chosen over the 2020 original because it engages the generative-AI/LLM era. Companion: the 2084 13-session Video Study for a flipped classroom. Two interleaved courses share one ethics spine; every 1–2 weeks ships one of 8 portfolio projects ("students don't study AI — they ship it").

Wk	Ethics seminar (Lennox)	AI Engineering (Rm 409/310)	Project shipped
1	Ch.1 Mapping the territory	Onboarding; Python/Git; local vs cloud LLM	— setup
2	Ch.2–3 Origins / surveillance	RAG chatbot on a local model (Rm 310 GPUs)	P1 Local RAG assistant
3–4	Ch.4–5 Narrow AI: promise & bias	CV classifier + bias/fairness audit; model cards	P2 CV model + bias audit
5	Ch.6 Upgrading humans	Voice agent; assistive-tech use case + fabricate device	P3 Assistive-tech AI device
6–7	Ch.7–8 AGI risk / personhood	Agentic workflow + guardrails; multimodal app deploy	P4 Agentic app w/ guardrails
8–9	Ch.9 Origin of moral sense	Eval harness; red-team; responsible-AI write-up	P5–P6 Eval + governance memo
10–12	Ch.10–13 Homo Deus / Revelation	Capstone: ship a campus tool (à la Campus Companion)	P7–P8 Capstone + demo day

Pricing model

- **Digital Pass — \$250–\$350 / student:** lab access, the local-AI toolchain, project templates, the eval harness, demo-board publishing, and a portfolio site.
- **Textbook — ~\$35:** 2084 and the AI Revolution (bulk/ministry discounts via 10ofThose).
- Two new courses: **AI Engineering + hands-on Machining/CNC** — reduces required external co-op hours.

Why it lands at Oakwood

As the only SDA HBCU, Oakwood can teach AI with a **worldview-grounded ethics voice** secular schools struggle to articulate — data dignity, human-in-the-loop, Sabbath as a model for digital rest. Graduates leave with a portfolio *and* a point of view.

12 · Fundraising, Match Funds & the Naming Opportunity

Grant & corporate funding

- **Federal HBCU + AI:** NSF ExpandAI, NSF HBCU-EiR, NSF HBCU-UP, Dept of Ed Title III Part B (Oakwood is an active recipient).
- **Compute/hardware programs:** NVIDIA Academic Grant, AMD University Program, Google.org / UNCF.
- **Mission-fit philanthropy:** John Templeton Foundation ("Religion, Science & Society — Intelligence"), Lilly Endowment (faith & AI), Mellon ("Unruly Intelligences").
- **Corporate matching-gift** programs for employee donations.

Notoriety & the naming track

- **Voices to engage:** Dr. James Tour, John Lennox, Wesley Huff — credible on AI + faith + science.
- **Channels:** Modern Wisdom, Valuetainment, Diary of a CEO — to spotlight an HBCU building responsible AI.
- **Naming opportunity:** "The John Lennox AI Innovation Lab" (pending Oakwood approval) — pairs the 2084 curriculum with a named-gift envelope that funds the grant-ineligible facility scope.

13 · Department-Wide Vision (donor / naming ask · \$245K–\$330K)

The full robust transformation — the envelope to put in front of a donor or match funder, since it carries the facility scope Title III cannot.

Division (full scope)	Range	Division (full scope)	Range
AI Studio compute (pooled · RTX PRO 6000)	\$42K–\$50K	Power / electrical (full dept)	\$34K–\$48K
Engineering Bambu fleet (full)	\$20K–\$23.9K	Structured cabling (80 drops + fiber)	\$24K–\$36K
Soldering + CNC (full)	\$11K–\$14K	Raised floor + Room-405 bathroom + room mod	\$45.6K–\$62K
Cameras (dept-wide) + Access (5 doors)	\$15K–\$19K	Network core, AV, furniture, software, permits	\$24K–\$30K
Department-Wide Vision — all-in (incl. GC markup + 10% IDC fee)			\$245,000–\$330,000

14 · Orchestration, Reporting & Next Steps

Single point of accountability

IDC engages and schedules every vendor & Huntsville sub, manages the grant vs. facility funding lanes, and owns the timeline. One markup, one fee, one invoice.

Live progress & reporting

A live HTML **progress dashboard** link is attached to the project email; **weekly & monthly** progress reports keep faculty & administration abreast through commissioning.

Protected investment

Department cameras + per-semester rotating access control + cabling/power done to code mean the equipment is controlled, managed, and protected from day one.

Open items to confirm before sealed bids

- Final room dimensions & seat count (Rm 409 measured pass) — required for the raised-floor quote.
- Campus-IT vendor ruling: UniFi/pfSense allowed, or map to Aruba/Cisco/Extreme? Does access tie to the campus card?
- Oakwood tax-exempt status + grant eligibility ruling (setup labor, software/SaaS, networking hardware, cabling labor, access hardware).
- Tier to commit: Recommended ~\$172K vs. a sub-\$170K trim (single-lab cameras / 2-door access).
- Stripe Payment Link + DocuSign send authorization; Gmail authorization for automated progress emails.

Recommended next step. Approve the Recommended Execution tier (~\$172,000 all-in), release the mobilization deposit, and authorize IDC to (1) commission the licensed-electrician load study and (2) issue the same scope to three sealed sub bids per trade. IDC returns firm, signed numbers within ~10 business days and begins the 90-day build.

Live reference hub: oakwood-ai-hub.vercel.app/ai-lab-final · Prepared by Island Development Crew LLC. Planning-grade; not a fixed bid until sealed sub quotes and the electrician load study are returned. Hardware prices are June-2026 and time-sensitive (2026 memory market) — re-quote within 14–30 days.

Authorized to proceed — Provider

Jonathan Isaac · Island Development Crew LLC

Signature / Date

Authorized to proceed — Client

Dr. Shushannah Smith · Oakwood University

Signature / Date